

Factsheet

ILA site

PoP – Fanø

(COBRA Fiber Optic Cable)



Location

Postvejen 40
6720 Fanø, Denmark

X- 55.398877

Y- 8.422977

Rack

Maximum power
supply pr. Rack 500W

CD 230 VAC (10A breaker)
for service purpose

Swivel frame for easy
access to the equipment

Grille for air intake in bottom
door

Rack with **lock** or
key combination

Grilles for air outlet on upper shelf, if
necessary the customer can replace the
top plate so that fans can be installed

PDU with A- and B feed 48 VDC, 8 hours at
maximum load, each -48VDC power supply
with main switch

Grilles for air outlet on upper shelf, if
necessary the customer can replace the
top plate so that fans can be installed

Hybride UPS system

48
VDC / 12 kW

230
VAC / 6 kVA

28x
Wing ESL180-12FTHT

480 Minutes
of autonomy at 2 kw

Commercial supply
directly from the
converter station

Actief monitoringssysteem Apollo / Iprotect

- Temperature
- Access system
- Humidity

- Smoke detection
- Leak detection
- Motion detector

- Camera surveillance
- **Note:** only real time

Layout

- A and B cooling (n + 1)
up to 15kW cooling effect

- Foam extinguisher, 6 liters
- First aid kit

- Cable tray system
fiberglass, 100mm



RelinedBV.
+31 (0)347 358 010
sales@relined.eu

RelinedGmbH
+49 (0)32 22 999 0075
sales@relined.eu